doyle + o'troithligh landscape architecture ltd.

North.

Note
See Planting drawings for all planting species, type, quantity, location and density.
See LD-01-PP for planting details.
See Softworks Specification for all planting and aftercare details.

TREATMENT 1 - to tree planting



FINISH GRASS/ SHRUBS

TOPSOIL
TOPSOILED, FERTILISED TO SPECIFICATION
SEE LANDSCAPE ARCHITECTS SPECIFICATION

SUBSOIL
- CLEAN SUBSOIL, FREE DRAINING, FREE FORM RUBBISH BUILDING CONTAMINATION, LARGE STONES ROCKS > 150MM
- LAID IN LAYERS MAX 250 - 300MM
- DEPTH VARIES TO MAKE UP SITE LEVELS AS PER ENGINEERS SPECIFICATION

SUB-FORMATION
(WHERE REQUIRED)
- REMOVE ALL DEBRIS, BUILDING CONTAMINATION, STONES/ ROCKS > 150MM FROM FORMATION SURFACE
- DECOMPACT DURING DRY WEATHER BY:
(i) BACK-ACTOR OF 'HYMAC' TO 450MM DEPTH; OR
(ii) 3-5 TYNE RIPPER MOUNTED ON CRAWLER TRACTOR @ 1200 CTR
- ASCERTAIN LOCATION OF ALL SERVICE RUNS PRIOR TO DECOMPACTION. WHERE AFFECTED, THEY SHALL BE SEELED OFF AND PROTECTED

NOTE
ALL GROUND PREPARATION TO ENGINEERS SPECIFICATION

TREATMENT 2 - to shrub planting areas



BARK MULCH APPLIED AFTER PLANTING IS FINISHED TO FINISH FLUSH WITH KERBING

TOPSOIL
TOPSOILED, FERTILISED TO SPECIFICATION
SEE LANDSCAPE ARCHITECTS SPECIFICATION

SUBSOIL
- CLEAN SUBSOIL, FREE DRAINING, FREE FORM RUBBISH BUILDING CONTAMINATION, LARGE STONES ROCKS > 150MM
- LAID IN LAYERS MAX 250 - 300MM
- DEPTH VARIES TO MAKE UP SITE LEVELS AS PER ENGINEERS SPECIFICATION

SUB-FORMATION
(WHERE REQUIRED)
- REMOVE ALL DEBRIS, BUILDING CONTAMINATION, STONES/ ROCKS > 150MM FROM FORMATION SURFACE
- DECOMPACT DURING DRY WEATHER BY:
(i) BACK-ACTOR OF 'HYMAC' TO 450MM DEPTH; OR
(ii) 3-5 TYNE RIPPER MOUNTED ON CRAWLER TRACTOR @ 1200 CTR

NOTE
ALL GROUND PREPARATION TO ENGINEERS SPECIFICATION

TREATMENT 3 - to grass planting areas



TOPSOILED, FERTILISED AND GRASS SEEDED
OR TURFED TO SPECIFICATION
TO FINISH 30MM ABOVE KERBING

SUBSOIL
- CLEAN SUBSOIL, FREE DRAINING, FREE FORM RUBBISH BUILDING CONTAMINATION, LARGE STONES ROCKS > 150MM
- LAID IN LAYERS MAX 250 - 300MM
- DEPTH VARIES TO MAKE UP SITE LEVELS AS PER ENGINEERS SPECIFICATION

SUB-FORMATION
- REMOVE ALL DEBRIS, BUILDING CONTAMINATION, STONES/ ROCKS > 150MM FROM FORMATION SURFACE

NOTE
ALL GROUND PREPARATION TO ENGINEERS SPECIFICATION

* NOTE: All topsoil to be inspected and approved by Landscape Architect prior to spreading / backfilling

D 01 LD-02-PP Topsoil depths to planted areas
Scale @ 1:20

Rev.	Date.	Note.

Project name:
Residential Development, Stoney Hill Road, Rathcoole

Project number: 18-008

Drawing name: Soft Landscape Details 02

Drawing number: LD-02-PP

Drawing scale @ A1:	Drawn by:	Checked by:
1:20	kg	ld

Status: Planning

date: 28.04.2020

Contact details:
Linda Doyle (Director) mobile: 087 267 4196
e-mail linda@doyle-otroithligh.com
Daithí oTroithligh (Director) mobile: 086 300 3499
e-mail daithi@doyle-otroithligh.com

Office address:
Pembroke House,
28-32 Upper Pembroke St.
Dublin 2.

doyle + o'troithligh
landscape - architecture

www.doyle-otroithligh.com